

City of Henderson
Standard Barricade Plan Notes

1. Access to all residences and businesses to be maintained at all times. Access to be determined in the field by existing conditions.
2. Any conflicting signs will be covered for the length of construction.
3. Contractor will be responsible for maintaining all school crossings and school-related signs. All set ups within a school zone will not be set up before 9:00 a.m. and will be picked up by 2:00 p.m. the same day, Monday through Friday unless otherwise noted.
4. No-parking signs to be placed 48 hours in advance to cover work area.
5. Contractor to maintain two 12-foot, smooth, dust-free detour lanes at all times.
6. Access for emergency vehicles to be maintained at all times.
7. All devices and set ups will be field adjusted as needed to meet existing conditions and will meet *Manual on Uniform Traffic Control Devices*. standards.
8. All equipment and material will be removed from right-of-way at the end of each day.
9. Contractor will backfill or plate during non-working hours.
10. If set up exceeds 72 hours, any shu-fly set up must be paved.
11. All excavations within 18 feet of the travel lane, deeper and wider than one foot and having less than 4:1 slope require barrier rail.
12. Contractor shall main a safe pedestrian route at all times.
13. Contractor will notify Traffic Services Maintenance (702- 267-3200) 48 hours prior to set up if working in or adjacent to a signalized intersection.
14. Contractor will coordinate with existing contractor to avoid conflicts.
15. Contractor will maintain bus stops and bus routes at all times. Call Citizens Area Transit (702-228-7433) or Clark County School District (702-799-8111) if additional information is needed.
16. Flagger stations shall be illuminated at night.
17. Will comply with NRS 484 and the latest edition of the *Manual on Uniform Traffic Control Devices*.
18. Hours of operation shall be in accordance with Chapter 8.84 of the Henderson Municipal Code, Public Peace and Safety - Noise Control.